

Department of Public Works

Infrastructure
Services Division
Facilities Development
& Management Section

INSTALLATION OF CARPETING, RESILIENT TILE, AND FLOORING ACCESSORIES FOR THE POLICE ADMINISTRATION BUILDING 7TH FLOOR OFFICE REMODELING

749 W. State Street Milwaukee, Wisconsin

February 2012

Project Number RM 5445 139010, RM 5445 1390111 Official Notice No. 35

CITY OF MILWAUKEE, WISCONSIN DEPARTMENT OF PUBLIC WORKS INFRASTRUCTURE SERVICES DIVISION

FACILITIES DEVELOPMENT & MANAGEMENT SECTION

PROJECT MANUAL

GOVERNING THE

INSTALLATION OF CARPETING, RESILIENT TILE,
AND FLOORING ACCESSORIES
FOR THE
POLICE ADMINISTRATION BUILDING
7TH FLOOR OFFICE REMODELING

749 W. STATE STREET
MILWAUKEE, WISCONSIN

Project No. **RM 5445 139010 RM 5445 139011**

February, 2012

TABLE OF CONTENTS

TABLE OF CONTENTS	PAGE NO.
BIDDING REQUIREMENTS	
00030 City of Milwaukee General Official Notice 00031 City of Milwaukee Specific Official Notice 00100 Instructions to Bidders	00030/1 00031/1 00100/1-2
GENERAL CONDITIONS	
00700 General Conditions 00821 Inspection Charges 00822 Prevailing Wage Scale 00850 Drawing Schedule	00700/1-4 00821/1 00822/1-32 00850/1
GENERAL REQUIREMENTS	
01010 Summary of Work 01210 Project Meetings 01300 Submittals and Permits 01500 Job Site Utilities, Facilities, and Security 01600 Materials and Equipment 01700 Cleaning and Project Close-Out	01010/1-2 01210/1-2 01300/1-2 01500/1-6 01600/1-3 01700/1-2
TECHNICAL SPECIFICATIONS	
09 65 00 Resilient Flooring 09 65 13 Resilient Base 09 68 13 Tile Carpeting	09 65 00/ 1-5 09 65 13/ 1-4 09 68 13/ 1-3

00030/1

CITY OF MILWAUKEE GENERAL OFFICIAL NOTICE TO CONTRACTORS

Separate sealed bids for each project will be received until 10:30 A.M. of the bid opening date at which time bids will be publicly opened and read for furnishing all material and doing all work for each project in accordance with the requirements of the respective Official Notice on the bid form furnished in accordance with plans, specifications, contract documents, and proposed form of contract on file in the office of the Department of Public Works, Municipal Building, 841 N. Broadway, Room 506, Milwaukee, Wisconsin, 53202.

PROSPECTIVE BIDDERS ARE TO CAREFULLY EXAMINE AND REVIEW ALL CONTRACT DOCUMENTS AND MATERIALS IN SAID OFFICE BEFORE SUBMITTING BID.

AFFIDAVITS OF NO INTEREST MUST ACCOMPANY THE BIDS, AND THE FAILURE OF PROSPECTIVE BIDDERS TO COMPLY WITH THESE REQUIREMENTS MAY DISQUALIFY THE BID.

THE CONTRACTOR/LESSEE AGREES TO COMPLY WITH ALL APPLICABLE REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT OF 1990, 42 U.S.C. § 12101, ET. SEQ. THE TDD NUMBER FOR PUBLIC WORKS IS (414) 286-2025.

As part of the bid each bidder shall submit a list of anticipated subcontractors and the class of work to be performed by each, which list should not be added to nor altered without the written consent of the Commissioner of Public Works.

All contractor(s) and subcontractor(s) are required to furnish or have on file a certificate of insurance in accordance with the insurance provisions of the General Specifications.

All contractor(s) and subcontractor(s) are subject to the prevailing wage rates and hours of labor as prescribed by the Common Council of the City of Milwaukee consistent with provisions of Section 66.293 of the Wisconsin Statutes.

Copies of the actual work classifications and wage and fringe benefit rates enforced on this project are available in Room 506 of the Municipal Building.

Corporate surety will be required on performance and payment bonds for all projects listed in the following Official Notices. All applicable charter and Statutory provisions and ordinances, all the provisions of this official notice, invitation to bid, general and detailed specifications, special provisions, proposal, schedule of fixed prices, addendum and plans for this project and all other contract documents set forth in the invitation to bid will be incorporated and made part of the contract as if therein set forth in full.

Tie bids, when the lowest ones, will be decided by the Commissioner of Public Works.

The Commissioner of Public Works reserves the right to reject any or all bids.

Signed: GHASSAN KORBAN, Commissioner of Public Works

Countersigned: MICHAEL J. DAUN, City Deputy Comptroller

CITY OF MILWAUKEE SPECIFIC OFFICIAL NOTICE NO. 35

Important Notice:

The Invitation to Bid, all bid documents and the Plans & Specifications for the project listed will be available electronically to prospective bidders via http://www.mpw.net/bids/docs/35-2012. Any required addenda or responses related to the listed projects will be posted on said website. Bidders are encouraged to utilize this electronic method of obtaining bid documents as the Department of Public Works intends to solely use this method for future projects. At this time however, a limited number of hard copies of the above documents will also be available at address listed below. IF YOU ONLY PRINT THE DOCUMENTS FROM THE WEBSITE AND WOULD LIKE YOUR COMPANY'S NAME PLACED ON THE PLAN HOLDERS' LIST, PLEASE CALL 414-286-3314.

Sealed bids will be opened on Thursday, March 08, 2012 at 10:30 A.M. for the INSTALLATION OF CARPETING, RESILIENT TILE, AND FLOORING ACCESSORIES FOR THE POLICE ADMINISTRATION BUILDING, located at 749 West State Street 7th Floor, Milwaukee, WI.

Bid Security Required: Bond, Certified Check, Cashier's Check, or Cash to accompany bid: 10% of Contractor's Base Bid

Time for Completion: 20 Working Days.

Liquidated Damages, per diem:

\$250,00

The MWSBE requirement for this project is 0% of the contract base bid. The residency requirement for this project is 40% of <u>all</u> hours worked on the project.

The apprenticeship requirements for this project are: N/A

The contractor shall specifically note the MWSBE, residency, and apprenticeship forms for this project. If the forms are not filled out properly, it will be cause for rejection of the bid.

Plans and project manual will be furnished to the prospective bidders upon payment of a \$10.00 non-refundable fee in room 506, Frank P. Zeidler Municipal Building, 841 North Broadway, Milwaukee, Wisconsin 53202. For general questions call 414-286-3314.

A \$10.00 per set additional non-refundable fee is required to obtain bid documents by mail. Plans are sent via U.S. mail unless other arrangements are made by the contractor.

Contractor must comply with all provisions of the CITY OF MILWAUKEE GENERAL OFFICIAL NOTICE TO CONTRACTORS published herein and at http://www.mpw.net/services/bids_home

<u>Pre-Bid Meeting:</u> A Pre-Bid Meeting is scheduled for Thursday, March 01, 2012, at 2:00 p.m. in Room 606 of the Frank P. Zeidler Municipal Building, 841 North Broadway, Milwaukee, Wisconsin. Bidder participation is urged to become familiar with all aspects of the project and bidding requirements.

Signed:

GHASSAN KORBAN Commissioner of Public Works

PUBLISH SIX (6) TIMES INSERTION WITHOUT FAIL, Thursday, February 23, 2012

\$ 115 Burn 18 5

SECTION 00100: INSTRUCTIONS TO BIDDERS

See also Instructions to Bidders in the "General Specifications" of the Department of Public Works, City of Milwaukee, Wisconsin, dated January 31, 1992, and all subsequent addenda.

BID FORM:

Submit a lump sum price for the work as indicated on the drawings and specified herein, complete in every respect.

Bids will not be accepted in any form except on the bid form included with this project manual.

The contractor must recognize and abide by the right of the Owner (City of Milwaukee) to accept or reject any or all bids in the best interests of the City.

ALTERNATE:

Each bidder shall examine the plans and project manual thoroughly to determine what extent the Alternate will affect the bid.

Alternate No.1:

State the amount to be added to the Base Bid to provide new flooring in Corridor 707 & 708 as indicated on the plans and as outlined in the Project Manual.

Alternate No.2:

State the amount to be added to the Base Bid to provide new flooring in Office 711 & 712 A as indicated on the plans and as outlined in the Project Manual.

CONTRACT AWARD:

The Commissioner of Public Works will award the contract on the basis of the Base Bid only or the Base Bid and the Alternate as funds permit.

CONTRACT BREAKDOWN:

Shortly after the award of the contract, each contractor shall submit a list showing the cost breakdown of the items in his contract. This list will be used as a basis for estimates of work completed for partial payment.

SITE VISIT:

All contractors shall visit the site, consult the drawings and project manual, be familiar with the work of other contractors and determine for himself all conditions affecting the work.

Failure by a contractor to be familiar with the project shall <u>not</u> release him from any obligation under this contract to complete the work in strict conformity with the plans and project manual and all City, State and Federal Codes or regulations pertaining to the work.

CONSTRUCTION START AND COMPLETION DATES

The start and completion dates are stated in the Specific Official Notice. The contractor may begin procuring materials and off-site fabricating (as appropriate and approved by Architect) on the date on the Notice to Proceed. The Notice to Proceed will be sent to the contractor directly following the signing of the contract.

00100/2

ADDITIONAL PLANS/PROJECT MANUALS

The successful contractor will be responsible for furnishing all additional copies of plans, project manuals, addenda, etc., as may be needed by the contractor and subcontractors. The City will cooperate by making originals available to the contractor's printer of choice.

SECTION 00700: GENERAL CONDITIONS

1. SCOPE:

A. Index:

- 1. Scope
- 2. DPW General Specifications
- Definitions
- 4. Control of Work and Materials
- 5. Samples and Tests
- 6. Project Coordination
- 7. Supervision of Work
- 8. Technical Specifications and Drawings
- 9. Safety Regulations
- 10. Code Rules

2. Department of Public Works General Specifications:

Provisions of the Department of Public Works General Specifications dated January 31, 1992, and subsequent addenda except as may be modified or expanded upon in this project manual, shall apply to all contractors and subcontractors working on the project. Copies of the General Specifications may be obtained from the Department of Public Works General Office, Room 501 Zeidler Municipal Building, 841 North Broadway, Milwaukee, Wisconsin, or from the Buildings & Fleet Services, Room 602, Zeidler Municipal Building.

3. <u>Definitions</u>:

- A. Owner: City of Milwaukee.
- B. Facilities Manager: The Facilities Manager of Buildings and Fleet Services.
- C. <u>Project Inspector</u>: The authorized representative of the Commissioner assigned to make detailed inspection of any or all portions of the work and materials thereof. These inspections are not a substitute to those required by the Department of Neighborhood Services for permit and code compliance.
- D. <u>Addenda</u>: Written or graphic instruments issued prior to the execution of the contract which modify or interpret the bidding documents, including drawings and project manual by additions, deletions, clarifications or corrections. Addenda will become part of the contract documents when the contract is executed.
- E. <u>Contract Drawings</u>: Drawings of the work to be done as listed hereafter in Section 00850 Drawing Schedule and/or Section 00870 Plans and Details.

REV 3/04

4. Control of Work and Materials:

A. <u>Detail and Shop Drawings</u>: Shop drawings and other additional drawings which may be required for each contract of the work shall be prepared by each respective contractor unless otherwise directed by the Facilities Manager. Prints shall be the same size as contract documents when practical. Prints of each drawing shall be submitted to the Facilities Manager for approval before proceeding with the work. Changes ordered by the Facilities Manager shall be made and revised prints submitted as above. The Facilities Manager's approval of drawings

- shall not relieve the contractor of responsibility for errors.
- B. Primary Lines and Grades: The City of Milwaukee will mark two building corners along a line and will establish a benchmark, with a relative elevation, within close proximity to the site. Once established by the City, the contractor shall preserve all points and benchmark as long as needed during construction. The contractor will bear all costs associated with re-establishing points and benchmark.
- C. Construction Lines and Grades: The contractor must bear sole responsibility for the correct transferal of all construction lines and grades from the primary lines and grades points. He shall take such measurements from existing work as may be necessary to insure the proper construction of his work.
- D. <u>Material Orders and Shipping Statements</u>: The contractor shall furnish to the Facilities Manager at least two (2) copies of all material orders and shipping statements. Itemized weights of the materials and individual units of finished work shall be shown.
- E. <u>Weighing of Materials and Fabricated Units</u>: The weighing of materials and fabricated units such as structural steel, casings, etc., when required, shall be done in the presence of the Commissioner's representative. The contractor shall be responsible for the satisfactory weighing of such materials and units.
- F. <u>Consignment and Delivery of Materials</u>: The materials for the work shall be consigned to the contractor and he shall be responsible for the delivery of all materials required for the completion of the contract.

5. Samples and Tests:

- A. Method of Sampling: Samples of the materials proposed or furnished for the work may be taken by the Commissioner at any time; at the point of manufacture, point of delivery or site of work. They will be selected, as far as practicable, in accordance with standard methods of sampling such materials as specified in the standard of the American Society for Testing Material. All sampling shall be done by authorized representatives of the Commissioner. Selections will be in an orderly and systematic manner, insuring samples representative of the lot.
- B. <u>A.S.T.M. Standards</u>: Wherever the abbreviation A.S.T.M. is used in connection with the number of a standard specification, the specification referred to shall be the Standard of the American Society for Testing Materials, designated by that number, including all revisions in effect on the date of award of the contract. Should a revised or amended standard be issued by the American Society for Testing Materials which, in the opinion of the Commissioner, conflicts with or causes undesirable changes in the standards referred to herein, the Commissioner reserves the right, by means of addenda to the project manual, to continue under the provisions of the pertinent standard referred to herein.
- C. Cost of Test Specimens and Samples: All test specimens of metals and all samples of non-metals required for tests shall be furnished by the contractor without cost to the City.
- D. <u>Costs of Tests</u>: All tests on test specimens of metals will be made at the expense of the contractor and the original test on samples of non-metals will be made at the expense of the City. In all cases, the testing procedure will be in accordance with Standard A.S.T.M. tests for such materials. Subsequent tests of non-metals requested by the contractor, when such tests are permitted by A.S.T.M. Specifications and approved by the Commissioner or subsequent tests ordered by the Commissioner will be made at the expense of the contractor.

6. <u>Project Coordination</u>:

- A. Contractors are required, so far as possible, to arrange work and to dispose of materials so as not to interfere with the work or storage of materials of other contractors or City forces engaged upon the work.
- B. Contractors shall give full cooperation to other trades and furnish any information necessary to permit the work of all trades to be installed satisfactorily and with the least possible interference or delay.
- C. Where the work of a contractor will be installed in close proximity to the work of other trades, or where there is evidence that the work of a contractor will interfere with the work of other trades, he shall assist in working out space conditions to make satisfactory adjustments.
- D. If a contractor installs work before coordinating it with other trades or so as to cause interference with work of other trades, he shall make necessary changes in his work to correct the condition without extra charge.
- E. Contractors are required to join their work to that of others in a proper manner, and in accordance with the spirit of the plans and project manual, and to perform the work in the proper sequence in relation to that of other contractors, and as may be directed by the Project Inspector.

7. Supervision of Work:

- A. Contractors shall furnish the services of an experienced engineer or superintendent.
- B. He shall be constantly in charge of the installation of the work together with all subcontractors, skilled workers, helpers, and labor required to unload, transfer, erect, connect up, adjust, start, operate and test each system.
- C. He shall be thoroughly acquainted with and be responsible for the various subcontractors' work so that it is properly coordinated and supervised to the satisfaction of the Commissioner of Public Works or his representative.
- D. Upon written notice to a contractor of the lack of such coordination and supervision, the Commissioner of Public Works may authorize such services as may be required and deduct the cost of this service at an hourly rate of \$60.00 per hour per worker from the contract for the work.

8. <u>Technical Specifications and Drawings</u>:

- A. Governing order of Contract Documents:
 - 1. The following provision modifies DPW General Specifications Item 2.1.3.1:

Anything mentioned in the Technical Specifications and not shown on the drawings or shown on the drawings and not mentioned in the Technical Specifications, shall be as if shown on or mentioned in both. In case of difference between drawings and Technical Specifications, the Technical Specifications shall govern. In case of any discrepancy in drawings or Technical Specifications, the matter shall be immediately submitted to Buildings & Fleet Services for decision. Said discrepancy shall <u>not</u> be adjusted by the contractor.

B. All contractors shall have complete sets of plans and project manuals on the job site at all times.

9. Safety Regulations:

UL

All work shall be done in accordance with the safety requirements referenced in the International Building Code, as adopted and amended by the State of Wisconsin and OSHA.

10. Code Rules:

The rulings, regulations and laws of the following shall be complied with in the completion of this project:

International Building Code, as amended and adopted by the State of Wisconsin Plumbing and Drainage Codes of the City of Milwaukee Ordinances of the City of Milwaukee National Board of Fire Underwriters OSHA NFPA FAA NEC IEEE

Rev. 3/04

00821/1

SECTION 00821: INSPECTION CHARGES

The contractor will be charged a fee for inspection for each and every day such inspection is required after the time allowed for completion has expired.

The amount of the fee for inspection shall be \$325.00 per day. *Rev. 2/08*

The time allowed for completion is stated in the Specific Official Notice and shall start with the date on the Notice to Proceed which will be sent to the contractor directly following the signing of the contract. The time allowed includes the time required for fabricating and procuring material and doing the work at the building site.

PREVAILING WAGE RATE DETERMINATION
Issued by the State of Wisconsin
Department of Workforce Development
Pursuant to s. 66.0903, Wis. Stats.
Issued On: 1/13/2012

	Issued On: 1/13/2012
DETERMINATION NU	MBER: 201200107
EXPIRATION DATE:	Prime Contracts MUST Be Awarded or Negotiated On Or Before 12/31/2012. If NOT, You MUST Reapply.
PROJECT NAME:	ALL PUBLIC WORKS PROJECTS UNDER SEC. 66.0903, STATSCITY OF MILWAUKEE
PROJECT LOCATION	: MILWAUKEE CITY, MILWAUKEE COUNTY, WI
CONTRACTING AGE	NCY: CITY OF MILWAUKEE-DEPT OF PUBLIC WORKS
CLASSIFICATION:	Contractors are responsible for correctly classifying their workers. Either call the Department of Workforce Development (DWD) with trade or classification questions or consult DWD's Dictionary of Occupational Classifications & Work Descriptions on the DWD website at: dwd.wisconsin.gov/er/prevailing_wage_rate/Dictionary/dictionary_main.htm.
OVERTIME:	Time and one-half must be paid for all hours worked: over 10 hours per day on prevailing wage projects over 40 hours per calendar week Saturday and Sunday on all of the following holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; The day before if January 1, July 4 or December 25 falls on a Saturday; The day following if January 1, July 4 or December 25 falls on a Sunday. Apply the time and one-half overtime calculation to whichever is higher between the Hourly Basic Rate listed on this project determination or the employee's regular hourly rate of pay. Add any applicable Premium or DOT Premium to the Hourly Basic Rate before calculating overtime. A DOT Premium (discussed below) may supersede this time and one-half requirement.
FUTURE INCREASE:	When a specific trade or occupation requires a future increase, you MUST add the full hourly increase to the "TOTAL" on the effective date(s) indicated for the specific trade or occupation.
PREMIUM PAY:	If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whevenever such pay is applicable.
DOT PREMIUM:	This premium only applies to highway and bridge projects owned by the Wisconsin Department of Transportation and to the project type heading "Airport Pavement or State Highway Construction." DO NOT apply the premium calculation under any other project type on this determination.
APPRENTICES:	Pay apprentices a percentage of the applicable journeyperson's hourly basic rate of pay and hourly fringe benefit contributions specified in this determination. Obtain the appropriate percentage from each apprentice's contract or indenture.
SUBJOURNEY:	Subjourney wage rates may be available for some of the trades or occupations indicated below with the exception of laborers, truck drivers and heavy equipment operators. Any employer interested in using a subjourney classification on this project MUST complete Form ERD-10880 and request the applicable wage rate from the Department of Workforce Development PRIOR to using the subjourney

worker on this project.

This document **MUST BE POSTED** by the **CONTRACTING AGENCY** in at least one conspicuous and easily accessible place **on the site of the project**. A local governmental unit may post this document at the place normally used to post public notices if there is no common site on the project. This document **MUST** remain posted during the entire time any worker is employed on the project and **MUST** be physically incorporated into the specifications and all contracts and subcontracts. If you have any questions, please write to the Equal Rights Division, Labor Standards Bureau, P.O. Box 8928, Madison, Wisconsin 53708 or call (608) 266-6861.

The following statutory provisions apply to local governmental unit projects of public works and are set forth below pursuant to the requirements of s. 66.0903(8), Stats.

- s. 66.0903 (1) (f) & s. 103.49 (1) (c) "PREVAILING HOURS OF LABOR" for any trade or occupation in any area means 10 hours per day and 40 hours per week and may not include any hours worked on a Saturday or Sunday or on any of the following holidays:
 - 1. January 1.
 - 2. The last Monday in May.
 - 3. July 4.
 - 4. The first Monday in September.
 - 5. The 4th Thursday in November.
 - 6. December 25.
 - 7. The day before if January 1, July 4 or December 25 falls on a Saturday.
 - 8. The day following if January 1, July 4 or December 25 falls on a Sunday.

s. 66.0903 (10) RECORDS; INSPECTION; ENFORCEMENT.

(a) Each contractor, subcontractor, or contractor's or subcontractor's agent performing work on a project of public works that is subject to this section shall keep full and accurate records clearly indicating the name and trade or occupation of every person performing the work described in sub. (4) and an accurate record of the number of hours worked by each of those persons and the actual wages paid for the hours worked.

s. 66.0903 (11) LIABILITY AND PENALTIES.

- (a) 1. Any contractor, subcontractor, or contractor's or subcontractor's agent who fails to pay the prevailing wage rate determined by the department under sub. (3) or who pays less than 1.5 times the hourly basic rate of pay for all hours worked in excess of the prevailing hours of labor is liable to any affected employee in the amount of his or her unpaid wages or his or her unpaid overtime compensation and in an additional amount as liquidated damages as provided under subd. 2., 3., whichever is applicable.
- 2. If the department determines upon inspection under sub. (10) (b) or (c) that a contractor, subcontractor, or contractor's or subcontractor's agent has failed to pay the prevailing wage rate determined by the department under sub. (3) or has paid less than 1.5 times the hourly basic rate of pay for all hours worked in excess of the prevailing hours of labor, the department shall order the contractor to pay to any affected employee the amount of his or her unpaid wages or his or her unpaid overtime compensation and an additional amount equal to 100 percent of the amount of those unpaid wages or that unpaid overtime compensation as liquidated damages within a period specified by the department in the order.
- 3. In addition to or in lieu of recovering the liability specified in subd. 1. as provided in subd. 2., any employee for and in behalf of that employee and other employees similarly situated may commence an action to recover that liability in any court of competent jurisdiction. If the court finds that a contractor, subcontractor, or contractor's or subcontractor's agent has failed to pay the prevailing wage rate determined by the department under sub. (3) or has paid less than 1.5 times the hourly basic rate of pay for all hours worked in excess of the prevailing hours of labor, the court shall order the contractor, subcontractor, or agent to pay to any affected employee the amount of his or her unpaid wages or his or her unpaid overtime compensation and an additional amount equal to 100 percent of the amount of those unpaid wages or that unpaid overtime compensation as liquidated damages. 5. No employee may be a party plaintiff to an action under subd. 3. unless the employee consents in writing to become a party and the consent is filed in the court in which the action is brought. Notwithstanding s. 814.04 (1), the court shall, in addition to any judgment awarded to the plaintiff, allow reasonable attorney fees and costs to be paid by the defendant.

BUILDING OR HEAVY CONSTRUCTION

Includes sheltered enclosures with walk-in access for the purpose of housing persons, employees, machinery, equipment or supplies and non-sheltered work such as canals, dams, dikes, reservoirs, storage tanks, etc. A sheltered enclosure need not be "habitable" in order to be considered a building. The installation of machinery and/or equipment, both above and below grade level, does not change a project's character as a building. On-site grading, utility work and landscaping are included within this definition. Residential buildings of four (4) stories or less, agricultural buildings, parking lots and driveways are NOT included within this definition.

	SKILLED TRADES			
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
404	Assuration Callium Tilla Installer	. 3		52.74
101	Acoustic Ceiling Tile Installer	33.43	19.31	
102	Boilermaker	31.09	21.87	52.96
103	Bricklayer, Blocklayer or Stonemason Future Increase(s): Add \$.50 on 6/01/2012; Add \$1.45/hr on 6/01/2013 Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	35.58	16.37	51.95
104	Cabinet Installer	29.06	15.16	44.22
105	Carpenter Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	33.43	19.31	52.74
106	Carpet Layer or Soft Floor Coverer	31.68	18.55	50.23
107	Cement Finisher	30.87	16.33	47.20
108	Drywall Taper or Finisher Future Increase(s): Add \$2.20/hr on 6/1/2012	28.97	17.74	46.71
109	Electrician Future Increase(s): Add \$1.40/hr on 6/1/2012. Add \$1.60/hr on 6/1/2013. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	31.54	20.95	52.49
110	Elevator Constructor	43.79	25.48	69.27
111	Fence Erector	27.00	0.00	27.00
112	Fire Sprinkler Fitter	36.82	19.03	55.85
113	Glazier	32.25	16.20	48.45
114	Heat or Frost Insulator	33.28	22.45	55.73

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY	HOURLY	
CODE	TRADE OR OCCUPATION	BASIC RATE OF PAY \$	FRINGE BENEFITS \$	TOTAL \$
115	Insulator (Batt or Blown)	23.62	11.55	35.17
116	Ironworker	31.31	21.54	52.85
117	Lather	31.68	18.41	50.09
118	Line Constructor (Electrical)	35.97	18.08	54.05
119	Marble Finisher	31.16	16.27	47.43
120	Marble Mason	35.53	15.92	51.45
121	Metal Building Erector	21.05	7.82	28.87
122	Millwright	28.30	23.29	51.59
123	Overhead Door Installer	26.53	0.00	26.53
124	Painter Future Increase(s): Add \$2.20/hr on 6/1/2012. Premium Increase(s): Add \$.20/hr for paperhanging; Add \$.35/hr for bridge,	28.97	17.74	46.71
	iron and drywall; Add \$.75/hr for spraying and sandblasting; Add \$.60/hr for EIFS work; Add \$1.00/hr for lead based paint removal.			
125	Pavement Marking Operator	26.00	0.00	26.00
126	Piledriver	28.11	23.94	52.05
127	Pipeline Fuser or Welder (Gas or Utility)	30.52	18.84	49.36
129	Plasterer	20.13	1.03	21.16
130	Plumber	36.97	17.47	54.44
132	Refrigeration Mechanic	37.21	19.04	56.25
133	Roofer or Waterproofer Future Increase(s): Add \$.50/hr. effective 06/01/2012	29.40	15.05	44.45
134	Sheet Metal Worker	37.20	16.37	53.57
135	Steamfitter	38.26	19.49	57.75
137	Teledata Technician or Installer Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	24.65	15.67	40.32
138	Temperature Control Installer	29.63	19.17	48.80
139	Terrazzo Finisher	18.00	5.35	23.35
140	Terrazzo Mechanic	31.16	16.27	47.43

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
141	Tile Finisher	23.76	16.05	39.81
142	Tile Setter	29.95	15.64	45.59
143	Tuckpointer, Caulker or Cleaner	34.30	15.55	49.85
144	Underwater Diver (Except on Great Lakes)	36.20	18.81	55.01
146	Well Driller or Pump Installer	25.32	15.30	40.62
147	Siding Installer	36.60	16.37	52.97
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	27.42	15.10	42.52
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	28.78	15.16	43.94
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	17.80	9.00	26.80
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	23.38	12.48	35.86
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.30	10.97	32.27
	TRUCK DRIVERS			-
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$
201	Single Axle or Two Axle	32.32	16.75	49.07
203	Three or More Axle Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	22.50	16.19	38.69
204	Articulated, Euclid, Dumptor, Off Road Material Hauler	33.32	17.60	50.92
205	Pavement Marking Vehicle	19.25	10.84	30.09
207	Truck Mechanic	24.91	15.35	40.26

	LABORERS					
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$		
301	General Laborer Premium Increase(s): Add \$.11 for mortar mixer, fork lift operator, air and electric equipment and power buggy operators; Add \$.22 for jackhammer operator, certified welder, gunite machineman.	28.82	15.61	44.43		
302	Asbestos Abatement Worker	21.58	17.83	39.41		
303	Landscaper	12.50	2.20	14.70		
310	Gas or Utility Pipeline Laborer (Other Than Sewer and Water)	19.14	15.53	34.67		
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased) Premium Increase(s): DOT PREMIUMS: Pay two times the hourly basic rate on New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	17.24	15.00	32.24		
314	Railroad Track Laborer	17.00	1.06	18.06		
CODE	HEAVY EQUIPMENT OPERATORS SITE PREPARATION, UTILITY OR LANDSCAPING Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION		HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$		
501	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Milling Machine; Boring Machine (Directional, Horizontal or Vertical); Backhoe (Track Type) Having a Mfgr's Rated Capacity of 130,000 Lbs. or Over; Backhoe (Track Type) Having a Mfgr's Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bulldozer or Endloader (Over 40 hp); Compactor (Self-Propelled 85 Ft Total Drum Width & Over, or Tractor Mounted, Towed & Light Equipment); Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Crane, Shovel, Dragline, Clamshells; Forklift (Machinery Moving or Steel Erection, 25 Ft & Over); Gradall (Cruz-Aire Type); Grader or Motor Patrol; Master Mechanic; Mechanic or Welder; Robotic Tool Carrier (With or Without Attachments); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Tractor (Scraper, Dozer, Pusher, Loader); Trencher (Wheel Type or Chain Type Having Over 8 Inch Bucket).		18.18	50.50		
502	Backfiller; Broom or Sweeper; Bulldozer or Endloader (Under 40 hp); Environmental Burner; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Jeep Digger; Screed (Milling Machine); Skid Rig; Straddle Carrier or Travel Lift; Stump Chipper; Trencher (Wheel Type or Chain Type Having 8 Inch Bucket & Under).	33.32	17.60	50.92		

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY	HOURLY	
CODE	TRADE OR OCCUPATION	BASIC RATE OF PAY \$	FRINGE BENEFITS \$	TOTAL \$
503	Air Compressor (&/or 400 CFM or Over); Augers (Vertical & Horizontal); Compactor (Self-Propelled 84 Ft Total Drum Width & Under, or Tractor Mounted, Towed & Light Equipment); Crusher, Screening or Wash Plant; Farm or Industrial Type Tractor; Forklift; Generator (&/or 150 KW or Over) Greaser; High Pressure Utility Locating Machine (Daylighting Machine); Mulcher; Oiler; Post Hole Digger or Driver; Pump (3 Inch or Over) or Well Points; Refrigeration Plant or Freeze Machine; Rock, Stone Breaker; Skid Steer Loader (With or Without Attachments); Vibratory Hammer or Extractor, Power Pack.		17.59	49.91
504	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	36.20	18.81	55.01
505	Work Performed on the Great Lakes Including Crane or Backhoe Operator; Assistant Hydraulic Dredge Engineer; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder; 70 Ton & Over Tug Operator. Premium Increase(s): Add \$.50/hr for friction crane, lattice boom or crane certification (CCO).	37.45	19.45	56.90
506	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	26.80	18.52	45.32
507	Work Performed on the Great Lakes Including Deck Equipment Operator, Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks - Great Lakes ONLY.	3	19.15	46.90
	HEAVY EQUIPMENT OPERATORS EXCLUDING SITE PREPARATION, UTILITY, PAVING L		VORK	
	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
CODE	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	TOTAL \$
508	Boring Machine (Directional); Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity of Over 4,000 Lbs., Crane With Boom Dollies; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Master Mechanic. Premium Increase(s): Crane Operators with CCO certification add \$.50/hr.	39.16	19.10	58.26

Crane Operators with CCO certification add \$.50/hr. Cranes with boom length over 200 ft. not exceeding 300 ft. OR lifting capacity over 200 ton not exceeding 300 ton add \$.50/hr. Over 300 ton OR 300 ft. add \$.01/hr. per foot OR ton whichever is greater.

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY	HOURLY	
CODE	TRADE OR OCCUPATION	BASIC RATE OF PAY \$	FRINGE BENEFITS \$	TOTAL \$
509	Backhoe (Track Type) Having a Mfgr's Rated Capacity of 130,000 Lbs. or Over; Boring Machine (Horizontal or Vertical); Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs. & Under; Crane, Towe Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Pile Driver; Versi Lifts, Tri-Lifts & Gantrys (20,000 Lbs. & Over). Premium Increase(s): Crane Operators with CCO certification add \$.50/hr.	38.66 r	19.10	57.76
510	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump (Over 46 Meter), Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Dredge (NOT Performing Work on the Great Lakes); Forklift (Machinery Moving or Steel Erection, 25 Ft & Over); Gradall (Cruz-Aire Type); Hydro-Blaster (10,000 PSI or Over); Milling Machine; Skid Rig; Traveling Crane (Bridge Type). Premium Increase(s): Crane Operators with CCO certification add \$.50/hr.	38.16	19.10	57.26
511	Air, Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Bulldozer or Endloader (Over 40 hp); Compactor (Self-Propelled 85 Ft Total Drum Width & Over, or Tractor Mounted, Towed & Light Equipment); Concrete Pump (46 Meter & Under), Concrete Conveyor (Rotec or Bidwell Type); Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Environmental Burner; Gantrys (Under 20,000 Lbs.); Grader or Motor Patrol; High Pressure Utility Locating Machine (Daylighting Machine); Manhoist; Material or Stack Hoist; Mechanic or Welder; Railroad Track Rail Leveling Machine, Tie Placer, Extractor, Tamper, Stone Leveler or Rehabilitation Equipment; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yd or More Capacity; Screed (Milling Machine); Sideboom; Straddle Carrier or Travel Lift; Tining or Curing Machine; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Trencher (Wheel Type or Chain Type Having Over 8-Inch Bucket). Premium Increase(s): Crane Operators with CCO certification add \$.50/hr.		19.10	57.26
512	Backfiller; Broom or Sweeper; Bulldozer or Endloader (Under 40 hp); Compactor (Self-Propelled 84 Ft Total Drum Width & Under, or Tractor Mounted, Towed & Light Equipment); Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Finishing Machine (Road Type); Fireman (Pile Driver & Derrick NOT Performing Work on the Great Lakes); Grout Pump; Hoist (Tugger, Automatic); Industrial Locomotives; Jeep Digger; Lift Slab Machine; Mulcher; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Screw or Gypsum Pumps; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Stump Chipper; Trencher (Wheel Type or Chain Type Having 8-Inch Bucket & Under); Winches & A-Frames.	37.47	19.10	56.57

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
513	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Boatmen (NOT Performing Work on the Great Lakes); Boiler (Temporary Heat); Crusher, Screening or Wash Plant; Elevator; Farm or Industrial Type Tractor; Fireman (Asphalt Plant NOT Performing Work on the Great Lakes); Forklift; Generator (&/or 150 KW or Over); Greaser; Heaters (Mechanical); Loading Machine (Conveyor); Oiler; Post Hole Digger or Driver; Prestress Machine; Pump (3 Inch or Over) or Well Points; Refrigeration Plant or Freeze Machine; Rock, Stone Breaker; Skid Steer Loader (With or Without Attachments); Vibratory Hammer or Extractor, Power Pack.		19.10	49.54
514	Gas or Utility Pipeline, Except Sewer & Water (Primary Equipment). Future Increase(s): Add \$2/hr. on 1/1/2013.	34.89	19.68	54.57
515	Gas or Utility Pipeline, Except Sewer & Water (Secondary Equipment).	31.26	17.40	48.66
516	Fiber Optic Cable Equipment	25.74	15.85	41.59

SEWER, WATER OR TUNNEL CONSTRUCTION

Includes those projects that primarily involve public sewer or water distribution, transmission or collection systems and related tunnel work (excluding buildings).

	SKILLED TRADES				
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE BENEFITS \$	TOTAL \$	
103	Bricklayer, Blocklayer or Stonemason	35.53	15.92	51.45	
105	Carpenter Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	33.43	19.31	52.74	
107	Cement Finisher Future Increase(s): Add \$1.86 on 6/1/12; Add \$1.87 on 6/1/13; Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.	27.14	19.22	46.36	
109	Electrician Future Increase(s): Add \$1.40/hr on 6/1/2012. Add \$1.60/hr on 6/1/2013. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	31.54	20.95	52.49	
111	Fence Erector	27.00	0.00	27.00	
116	Ironworker Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	31.31	22.22	53.53	
118	Line Constructor (Electrical)	35.97	18.08	54.05	
125	Pavement Marking Operator	26.00	0.00	26.00	
126	Piledriver	28.11	23.94	52.05	
130	Plumber	36.18	16.86	53.04	
135	Steamfitter	35.81	19.04	54.85	
137	Teledata Technician or Installer	24.65	15.17	39.82	

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE <u>BENEFITS</u> \$	TOTAL
143	Tuckpointer, Caulker or Cleaner	34.30	15.55	49.85
144	Underwater Diver (Except on Great Lakes)	36.20	18.81	55.01
146	Well Driller or Pump Installer	24.22	14.80	39.02
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	27.42	15.10	42.52
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	28.78	15.16	43.94
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	17.80	9.00	26.80
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	23.38	12.48	35.86
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.30	10.97	32.27
	TRUCK DRIVERS		L. L	
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL
201	Single Axle or Two Axle	23.00	8.64	31.64
203	Three or More Axle	17.54	13.41	30.95
204	Articulated, Euclid, Dumptor, Off Road Material Hauler Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	22.50	16.19	38.69
205	Pavement Marking Vehicle	19.25	10.84	30.09
207	Truck Mechanic	17.54	13.41	30.95
	LABORERS			
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$
301	General Laborer Future Increase(s): Add \$1.73/hr on 6/4/2012. Premium Increase(s): Add \$1.92 for bottomman; Add \$2.03 for concrete	27.72	15.61	43.33

Add \$1.92 for bottomman; Add \$2.03 for concrete manhole builder, bracer, jointman, or pipelayer; Add \$4.83 for blaster. Add \$2.00 for all tunnel work under 15 lbs. compressed air; Add \$2.00 for 0-30 lbs. compressed air; Add \$3.00 for over 30 lbs. compressed

air.

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE <u>BENEFITS</u> \$	TOTAL \$
303	Landscaper	12.50	2.20	14.70
304	Flagperson or Traffic Control Person	22.50	12.90	35.40
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.09	14.40	31.49
314	Railroad Track Laborer	17.00	1.06	18.06
	HEAVY EQUIPMENT OPERATORS SEWER, WATER OR TUNNEL WOR			
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
521	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Master Mechanic; Pile Driver. Premium Increase(s): Crane Operators with CCO certification add \$.50/hr. Cranes with boom length over 200 ft. not exceeding 300 ft. OR lifting capacity over 200 ton not exceeding 300 ton add \$.50/hr. Over 300 ton OR 300 ft. add \$.01/hr. per foot OR ton whichever is greater.	39.16	19.10	58.26
522	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Boring Machine (Directional); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump (Over 46 Meter), Concrete Conveyor (Rotec or Bidwell Type); Concrete Spreader & Distributor; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With a Lifting Capacity of 4,000 Lbs. & Under; Dredge (NOT Performing Work on the Great Lakes); Milling Machine; Skid Rig; Telehandler; Traveling Crane (Bridge Type). Future Increase(s): Add \$2.05/hr on 6/4/2012. Premium Increase(s): Add \$2.25/hr for operating tower crane.		18.55	52.46

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
CODE	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	TOTAL \$
523	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Boring Machine (Horizontal or Vertical); Bulldozer or Endloader (Over 40 hp); Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Concrete Pump (46 Meter & Under), Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Hydro-Blaster (10,000 PSI or Over); Manhoist; Material or Stack Hoist; Mechanic or Welder; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yd or More Capacity; Screed (Milling Machine); Sideboom; Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Trencher (Wheel Type or Chain Type Having Over 8-Inch Bucket). Future Increase(s): Add \$2.05/hr on 6/4/2012. Premium Increase(s): Add \$.25/hr for operating tower crane.		18.55	51.51
524	Backfiller; Broom or Sweeper; Bulldozer or Endloader (Under 40 hp); Compactor (Self-Propelled 85 Ft Total Drum Width & Over, or Tractor Mounted, Towed & Light Equipment); Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Finishing Machine (Road Type); Environmental Burner; Fireman (Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Hoist (Tugger, Automatic); Grout Pump; Jeep Digger; Lift Slab Machine; Mulcher; Power Subgrader; Pump (3 Inch or Over) or Well Points; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Screw or Gypsum Pumps; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Stump Chipper; Tining or Curing Machine; Trencher (Wheel Type or Chain Type Having 8-Inch Bucket & Under); Winches & A-Frames.	30.89	18.12	49.01
525	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Compactor (Self-Propelled 84 Ft Total Drum Width & Under, or Tractor Mounted, Towed & Light Equipment); Crusher, Screening or Wash Plant; Farm or Industrial Type Tractor; Fireman (Asphalt Plant NOT Performing Work on the Great Lakes); Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Loading Machine (Conveyor); Post Hole Digger or Driver; Refrigeration Plant or Freeze Machine; Rock, Stone Breaker; Skid Steer Loader (With or Without Attachments); Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$2.05/hr on 6/4/2012. Premium Increase(s): Add \$.25/hr for operating tower crane.	30.51	18.55	49.06
526	Boiler (Temporary Heat); Forklift; Greaser; Oiler.	29.44	18.10	47.54
527	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	36.20	18.81	55.01

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE <u>BENEFITS</u> \$	TOTAL \$
528	Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	36.20	18.81	55.01
529	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	26.80	18.52	45.32
530	Work Performed on the Great Lakes Including Deck Equipment Operator; Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under), Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks - Great Lakes ONLY.	3	18.52	45.32

AIRPORT PAVEMENT OR STATE HIGHWAY CONSTRUCTION

Includes all airport projects (excluding buildings) and all projects awarded by the Wisconsin Department of Transportation (excluding buildings).

	SKILLED TRADES			***
<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
103	Bricklayer, Blocklayer or Stonemason	32.66	15.92	48.58
105	Carpenter Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	33.43	19.31	52.74
107	Cement Finisher Future Increase(s): Add \$1.86 on 6/1/12; Add \$1.87 on 6/1/13; Add \$1.87 on 6/1/14; Add \$1.87 on 6/1/15; Add \$1.75 on 6/1/16. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.40/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.	29.33	17.03	46.36
109	Electrician	31.64	23.78	55.42
111	Fence Erector	35.62	0.00	35.62
116	Ironworker	31.31	21.54	52.85
118	Line Constructor (Electrical)	35.97	18.08	54.05
124	Painter	27.87	14.39	42.26
125	Pavement Marking Operator	27.87	14.39	42.26
126	Piledriver Premium Increase(s): Add \$.65/hr for Piledriver Loftsman; Add \$.75/hr for Sheet Piling Loftsman. DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	29.56	24.96	54.52
133	Roofer or Waterproofer	28.85	14.60	43.45
137	Teledata Technician or Installer	24.65	15.17	39.82
143	Tuckpointer, Caulker or Cleaner	34.30	15.55	49.85
144	Underwater Diver (Except on Great Lakes)	36.20	18.81	55.01

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY	HOURLY	
CODE	TRADE OR OCCUPATION	BASIC RATE OF PAY \$	FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	33.87	16.10	49.97
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY Premium Increase(s):	29.64	14.64	44.28
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.18	13.07	38.25
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	23.38	12.48	35.86
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.30	10.97	32.27
	TRUCK DRIVERS		W -	
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL
201	Single Axle or Two Axle Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	22.35	16.19	38.54
203	Three or More Axle	24.91	15.63	40.54
204	Articulated, Euclid, Dumptor, Off Road Material Hauler Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	22.50	16.19	38.69
205	Pavement Marking Vehicle	23.84	14.70	38.54
206	Shadow or Pilot Vehicle	24.76	15.35	40.11
207	Truck Mechanic	24.91	15.63	40.54

31.49

18.06

14.40

1.06

	LABORERS					
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$		
		· · · · · · · · · · · · · · · · · · ·		· ·		
301	Future Increase(s): Add \$1.60/hr on 6/1/2012: Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014. Premium Increase(s): Add \$.15/hr for air tool operator, joint sawer and filler (pavement), vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.35/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.50/hr for line and grade specialist; Add \$.65/hr for blaster and powderman; Add \$2.01/hr for topman; Add \$2.46/hr for bottomman; Add \$3.23/hr for pipelayer. / DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	24.34	17.85	42.19		
302	Asbestos Abatement Worker	22.00	16.86	38.86		
303	Landscaper	23.71	15.03	38.74		
304	Flagperson or Traffic Control Person Future Increase(s): Add \$1.60/hr on 6/1/2012; Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.	20.83	17.85	38.68		

17.09

17.00

Fiber Optic Laborer (Outside, Other Than Concrete Encased)

311

314

Railroad Track Laborer

HEAVY EQUIPMENT OPERATORS AIRPORT PAVEMENT OR STATE HIGHWAY CONSTRUCTION

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
CODE	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	TOTAL \$
531	Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type). Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	34 <u>,</u> 22	18.90	53.12
532	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or	33.72	18.90	52.62

Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver.

Future Increase(s):

Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.

Premium Increase(s):

DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).

HOURI V

CODE	TRADE OR OCCUPATION	BASIC RATE OF PAY \$	FRINGE BENEFITS \$	TOTAL \$
533	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs.)		18.90	52.12

HOHDLY

& Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane WIth a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A-Frames.

Frings Banefite Must Ba Paid On All Hours Worked

Future Increase(s):

Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.

Premium Increase(s):

DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
CODE	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	<u>TOTAL</u> \$
534	Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	32.96	18.90	51.86
535	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boller (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	32.67	18.90	51.57
536	Fiber Optic Cable Equipment.	24.39	15.45	39.84
537	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	36.20	18.81	55.01

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE	
CODE	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	TOTAL \$
538	Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	36.20	18.81	55.01
539	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or More); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	26.80	18.52	45.32
540	Work Performed on the Great Lakes Including Deck Equipment Operator, Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks-Great Lakes ONLY.	S	18.52	45.32

LOCAL STREET OR MISCELLANEOUS PAVING CONSTRUCTION

includes roads, streets, alleys, trails, bridges, paths, racetracks, parking lots and driveways (except residential or agricultural), public sidewalks or other similar projects (excluding projects awarded by the Wisconsin Department of Transportation).

	SKILLED TRADES				
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$	
103	Bricklayer, Blocklayer or Stonemason	35.53	15.92	51.45	
105	Carpenter	29.06	15.16	44.22	
107	Cement Finisher	27.57	16.33	43.90	
109	Electrician Future Increase(s): Add \$.50/hr. effective 06/04/2012. Premium Increase(s): DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.	28.74	17.86	46.60	
111	Fence Erector	27.00	0.00	27.00	
116	Ironworker	31.31	21.54	52.85	
118	Line Constructor (Electrical)	35.97	18.08	54.05	
124	Painter	28.47	16.74	45.21	
125	Pavement Marking Operator	26.00	0.00	26.00	
126	Piledriver	28.11	23.94	52.05	
133	Roofer or Waterproofer	28.85	14.60	43.45	
137	Teledata Technician or Installer	24.65	15.17	39.82	
143	Tuckpointer, Caulker or Cleaner	34.30	15.55	49.85	
144	Underwater Diver (Except on Great Lakes)	36.20	18.81	55.01	
150	Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.42	12.90	48.32	
151	Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	28.78	14.42	43.20	
152	Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.18	13.07	38.25	
153	Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	23.38	12.48	35.86	
154	Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.30	10.97	32.27	

	TRUCK DRIVERS			
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE <u>BENEFITS</u> \$	TOTAL
201	Single Axle or Two Axle	15.00	0.00	15.00
203	Three or More Axle	20.00	6.00	26.00
204	Articulated, Euclid, Dumptor, Off Road Material Hauler Future Increase(s): Add \$1/hr on 6/3/2012; Add \$1/hr on 6/2/2013.	31.89	17.98	49.87
205	Pavement Marking Vehicle	19.25	10.84	30.09
206	Shadow or Pilot Vehicle	15.00	0.00	15.00
207	Truck Mechanic	20.00	6.00	26.00
	LABORERS		······································	
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked <u>TRADE OR OCCUPATION</u>	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
301	General Laborer	21.73	17.04	38.77
303	Landscaper	22.96	15.37	38.33
304	Flagperson or Traffic Control Person Future Increase(s): Add \$1.60/hr on 6/1/2012; Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.	23.55	13.45	37.00
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.09	14.40	31.49
314	Railroad Track Laborer	17.00	1.06	18.06

HEAVY EQUIPMENT OPERATORS CONCRETE PAVEMENT OR BRIDGE WORK

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE <u>BENEFITS</u> \$	<u>TOTAL</u> \$
541	Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Master Mechanic. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	34.22	18.90	53.12
542	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With a Lifting Capacity of 4,000 Lbs. & Under; Crane, Tower Crane Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot		18.90	52.62

Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.

(NOT Performing Work on the Great Lakes); Pile Driver.

Premium Increase(s):

DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY BASIC RATE	HOURLY FRINGE		
CODE	TRADE OR OCCUPATION	OF PAY \$	BENEFITS \$	TOTAL \$	
543	Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradal (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Manhoist; Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A-Frames.		18.22	50.11	
544	Backfiller; Belting, Burlap, Texturing Machine; Broom or Sweeper;	33.22	18.90	52.12	

Backfiller; Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Jeep Digger; Joint Sawer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Self Propelled Chip Spreader: Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine.

Future Increase(s):
Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.

Premium Increase(s):

DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$
545	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack.		17.58	48.00
546	Fiber Optic Cable Equipment.	24.39	15.45	39.84
547	Work Performed on the Great Lakes Including Diver; Wet Tender or Hydraulic Dredge Engineer.	36.20	18.81	55.01
548	Work Performed on the Great Lakes Including 70 Ton & Over Tug Operator; Assistant Hydraulic Dredge Engineer; Crane or Backhoe Operator; Hydraulic Dredge Leverman or Diver's Tender; Mechanic or Welder.	36.20	18.81	55.01
549	Work Performed on the Great Lakes Including Deck Equipment Operator or Machineryman (Maintains Cranes Over 50 Tons or Backhoes 115,000 Lbs. or more); Tug, Launch or Loader, Dozer or Like Equipment When Operated on a Barge, Breakwater Wall, Slip, Dock or Scow, Deck Machinery.	26.80	18.52	45.32
550	Work Performed on the Great Lakes Including Deck Equipment Operator; Machineryman or Fireman (Operates 4 Units or More or Maintains Cranes 50 Tons or Under or Backhoes 115,000 Lbs. or Under); Deck Hand, Deck Engineer or Assistant Tug Operator; Off Road Trucks - Great Lakes ONLY.		18.52	45.32
	HEAVY EQUIPMENT OPERATORS ASPHALT PAVEMENT OR OTHER WO			
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE <u>BENEFITS</u> \$	TOTAL \$
551	Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self Erecting Tower Crane With a Lifting Capacity of Over 4,000 Lbs., Crane With Boom Dollies; Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads and/or Jib Lengths Measuring 176 Ft or Over; Master Mechanic.	38.06	18.10	56.16

Defetti	ination No. 201200107			-aye 21 01 32
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	TOTAL \$
552	Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With a Lifting Capacity Of 4,000 Lbs. & Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Increase(s): DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).		18.90	52.62
553	Air, Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boring Machine (Directional, Horizontal or Vertical); Bulldozer or Endloader; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Laser/Screed; Concrete Slipform Placer Curb & Gutter Machine; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or	31.52	17.50	49.02

Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boring Machine (Directional, Horizontal or Vertical); Bulldozer or Endloader; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Conveyor System; Concrete Laser/Screed; Concrete Slipform Placer Curb & Gutter Machine; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Manhoist; Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Railroad Track Rail Leveling Machine, Tie Placer, Extractor, Tamper, Stone Leveler or Rehabilitation Equipment; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A-Frames.

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$
554	Backfiller; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self-Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.	32,67	18.55	51.22
555	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oller; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.		18.55	51.22
556	Fiber Optic Cable Equipment.	24.39	15.45	39.84

RESIDENTIAL OR AGRICULTURAL CONSTRUCTION

Includes single family houses or apartment buildings of no more than four (4) stories in height and all buildings, structures or facilities that are primarily used for agricultural or farming purposes, excluding commercial buildings. For classification purposes, the exterior height of a residential building, in terms of stories, is the primary consideration. All incidental items such as site work, driveways, parking lots, private sidewalks, private septic systems or sewer and water laterals connected to a public system and swimming pools are included within this definition. Residential buildings of five (5) stories and above are NOT included within this definition.

	SKILLED TRADES					
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE BENEFITS \$	TOTAL \$		
101	Acoustic Ceiling Tile Installer	27.00	1.16	28.16		
102	Boilermaker	31.09	21.87	52.96		
103	Bricklayer, Blocklayer or Stonemason	26.22	13.80	40.02		
104	Cabinet Installer	26.00	2.33	28.33		
105	Carpenter	31.68	7.03	38.71		
106	Carpet Layer or Soft Floor Coverer	21.40	6.01	27.41		
107	Cement Finisher	28.00	10.10	38.10		
108	Drywall Taper or Finisher Future Increase(s): Add \$2.20/hr on 6/1/2012	28.97	17.74	46.71		
109	Electrician	31.10	6.01	37.11		
110	Elevator Constructor	43.79	25.48	69.27		
111	Fence Erector	17.64	4.66	22.30		
112	Fire Sprinkler Fitter	36.39	16.97	53.36		
113	Glazier	36.23	8.04	44.27		
114	Heat or Frost Insulator	29.04	19.73	48.77		
115	Insulator (Batt or Blown)	11.00	2.51	13.51		
116	Ironworker	23.05	4.06	27.11		
117	Lather	28.15	15.14	43.29		
119	Marble Finisher	31.16	16.27	47.43		
120	Marble Mason	35.53	15.92	51.45		
121	Metal Building Erector	15.19	2.00	17.19		
123	Overhead Door Installer	23.00	8.00	31.00		
124	Painter	23.00	2.81	25.81		

CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE <u>OF PAY</u> \$	HOURLY FRINGE BENEFITS \$	TOTAL \$			
125	Pavement Marking Operator	26.00	0.00	26.00			
129	Plasterer	30.36	7.15	37.51			
130	Plumber	37.42	17.92	55.34			
132	Refrigeration Mechanic	25.00	0.51	25.51			
133	Roofer or Waterproofer Future Increase(s): Add \$.50/hr. effective 06/01/2012	29.40	15.05	44.45			
134	Sheet Metal Worker	28.15	15.14	43.29			
135	Steamfitter	32.59	11.05	43.64			
137	Teledata Technician or Installer	19.23	5.32	24.55			
138	Temperature Control Installer	22.00	2.64	24.64			
139	Terrazzo Finisher	18.00	5.35	23.35			
140	Terrazzo Mechanic	31.16	16.27	47.43			
141	Tile Finisher	23.96	15.50	39.46			
142	Tile Setter	27.00	1.91	28.91			
143	Tuckpointer, Caulker or Cleaner	32.50	1.62	34.12			
146	Well Driller or Pump Installer	27.60	0.00	27.60			
147	Siding Installer	16.00	0.00	16.00			
	TRUCK DRIVERS						

	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked	HOURLY	HOURLY		
CODE	TRADE OR OCCUPATION	BASIC RATE OF PAY \$	FRINGE <u>BENEFITS</u> \$	TOTAL \$	
201	Single Axle or Two Axle	16.25	2.25	18.50	
203	Three or More Axle	17.00	7.63	24.63	
205	Pavement Marking Vehicle	19.25	10.84	30.09	
207	Truck Mechanic	19.00	1.75	20.75	

•	LABORERS			
CODE	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE BENEFITS \$	<u>TOTAL</u> \$
301	General Laborer	17.50	6.16	23.66
302	Asbestos Abatement Worker	17.00	2.21	19.21
303	Landscaper	11.00	2.07	13.07
311	Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.09	14.40	31.49
	HEAVY EQUIPMENT OPERATORS RESIDENTIAL OR AGRICULTURAL CONST			
<u>CODE</u>	Fringe Benefits Must Be Paid On <u>All</u> Hours Worked TRADE OR OCCUPATION	HOURLY BASIC RATE OF PAY \$	HOURLY FRINGE <u>BENEFITS</u> \$	TOTAL \$
557	Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Backhoe (Track Type); Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boring Machine (Directional, Horizontal or Vertical); Bulldozer or Endloader; Concrete Breaker (Large, Auto, Vlbratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Crane, Shovel, Dragline, Clamshells; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Manhoist; Material or Stack Hoist; Mechanic or Welder; Milling Machine; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Tractor (Scraper, Dozer, Pusher, Loader); Tractor or Truck Mounted Hydraulic Backhoe; Tractor or Truck Mounted Hydraulic Crane (10 Tons or Under); Trencher (Wheel Type or Chain Type); Wlnches & A-Frames.	32.56	10.76	43.32
558	Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Backfiller; Belting, Burlap, Texturing Machine; Boiler (Temporary Heat); Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Farm or Industrial Type Tractor; Forklift; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Jeep Digger; Lift Slab Machine; Mulcher; Oiler; Post Hole Digger or Driver; Power Subgrader; Pump (3 Inch or Over) or Well Points; Robotic Tool Carrier (With or Without Attachments); Rock, Stone Breaker; Roller (Rubber Tire, 5 Tons or Under); Screed (Milling Machine); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Stump Chipper; Telehandler; Vibratory Hammer		0.44	17.84

or Without Attachments); Stump Chipper; Telehandler; Vibratory Hammer

or Extractor, Power Pack.

Defer	minat	ion No	. 2012	NN 1N 7
Delei	11111112	KHI WC		

Page 32 of 32

00850/1

SECTION 00850: DRAWING SCHEDULE

The following listed drawings accompany and form a part of the project contract documents along with this project manual and generally illustrate the nature of the work.

See Section 00870 for additional drawings which are included within this project manual.

Sheet No.

Architectural Drawings

A 127

Flooring Plans and Finish Schedules

SECTION 01010: SUMMARY OF WORK:

SCOPE:

A. Index:

- 1. Scope
- 2. Project Description
- 3. Work by Others
- 4. Scheduling of Work

2. PROJECT DESCRIPTION:

- A. The south office area being remodeled will be vacant during construction. Installation of the flooring in the north office area shall be coordinated with the City to be completed in 2 phases.
- B. The project includes the installation of carpeting, resilient tile, and flooring accessories.
- C. The following outline is intended to serve as a general guide only, and not as a complete listing of work, operations, or materials. Consult the Table of Contents for a complete listing of items included.
 - 1. Prepare existing floor for installation including stripping and cleaning and leveling according to manufacturer's recommendations. Removal of existing carpet flooring required for alternate bid in offices 711 & 712.
 - 2. Install wall base at walls and at columns. (Straight base at carpet tile and cove base at VCT.)
 - 3. Install carpet tiles.
 - 4. Prepare surface of existing surface as required at resilient tile floor.
 - 5. Install resilient tile flooring and accessories as indicated on plans.

D. Examine Documents and Visit Site:

- Before submitting a bid proposal, bidders should carefully examine the drawings and specifications; fully inform themselves as to all existing conditions and limitations, including those of labor; and shall include in the bid proposal a sum sufficient to cover the cost of all items contemplated by the construction documents.
- Any site visits to determine existing conditions must be coordinated through the Project Architect (Contact) and scheduled through the City/Police Department. Contractor is responsible to allow appropriate time for scheduling a site visit to review site conditions and incorporate those conditions that may impact the cost into their final bid.
- 4. Additional charges will not be as considered for work which, prior to bidding, could reasonably be inferred as appropriate by examination of the drawings and specifications, visiting the site, and closely reviewing the work as indicated above. No representations as to subsurface conditions are made.

3. WORK BY OTHERS:

- A. General construction, electrical, communications and data systems.
- B. Removal of existing vinyl tile at location of **new resilient floor only** by others.

4. <u>SCHEDULING OF WORK</u>:

- A. The contractor shall provide a construction schedule which includes all phases of construction, indicating the anticipated start and completion times for each of those phases. The contractor shall provide that complete schedule at the Pre-Construction Meeting arranged by the City.
- B. Installation may take place during office hours if said installation does not generate noise, dust, or objectionable odors. Installation involving noise or creating dust or objectionable odors shall take place before or after regular office hours or on Saturday.

SECTION 01210: PROJECT MEETINGS

1. SCOPE:

A. Index:


- Scope
- 2. Pre-Construction Meeting
- 3. Progress Meetings

2. <u>PRE-CONSTRUCTION MEETING</u>:

- A. Soon after the award of the contract and prior to the start of construction, the contractor shall attend a pre-construction conference with representatives of the City.
- B. The contractor shall have at the meeting responsible representatives from subcontractors who are to perform major work on the project.
- C. The purpose of the meeting is to discuss in detail the plans and specifications. The discussion shall include:
 - Schedule
 - 2. Equipment
 - 3. Material Storage
 - 4. Traffic Control
 - 5. Inspection Requirements
 - 6. Protection Procedures for the structure, adjacent facilities, environment, and personnel.
 - 7. Hours of Work
- D. The contractor shall submit the construction schedule to the architect/engineer at this meeting and a listing of subcontractors and their work. The contractor shall describe, in detail, when each portion of the work is expected to be accomplished. The subcontractors shall participate in the discussion. The architect/engineer will serve to interpret the contract documents should such questions arise.
- E. Any other questions that the contractor or his subcontractors have about the work or its scheduling shall be raised at these meetings.
- F. Requirements for contract administration and construction operations will be defined for participants.
- G. The architect/engineer will determine time, date, and place of the meeting.

3. PROGRESS MEETINGS:

- Bi-weekly meetings will be held for the purpose of coordinating and expediting the work.
- B. Attendance at project meetings by the contractor is mandatory. These meetings shall also be attended by representatives of each subcontractor who is either working at the site or is affected by work being done at the site. The contractor shall submit an updated construction schedule at these meetings and a short narrative should be written, describing the cause of any delays and intended action to remedy these delays.



SECTION 01300: SUBMITTALS/PERMITS

1. SCOPE:

A. Index:

- 1. Scope
- 2. Submittals
- 3. Permits
- 4. Inspection

2. SUBMITTALS:

- A. Comply with the requirements of the General Conditions and as follows:
 - 1. Forward Submittals not more than 20 calendar days after the Notice to Proceed date. No work, as indicated on any shop drawing, samples, hardware list, etc., shall be started until those submittals have been reviewed and work authorized.
 - 2. All submittals must be thoroughly reviewed by the prime contractor for conformance to contract documents, prior to submission to the City, or its agents, for review. Shop drawings and catalog information shall be stamped "Reviewed By" and signed by the contractor's reviewer. The prime contractor shall review all subcontractor submittals prior to submittal to the City for compliance with contract documents and to coordinate all work.
 - 3. Include with each submittal a transmittal letter signed and dated by the prime contractor containing the following:
 - a. Name of Contractor
 - b. Name of Project
 - c. List of Submittals
 - d. Name of Manufacturer or Supplier
 - e. Additional information as required for the items being provided.
- B. Shop Drawings, Catalog Information, Calculations, and Samples:
 - Shop Drawings: Submit one blue/black line print review. The City will notify the contractor in writing and return one copy marked "REVIEWED NO EXCEPTIONS TAKEN" with minor or no notations. The City will also notify the contractor in writing and return one copy, along with comments, when the drawings are marked either "REJECTED" or "REVISE AND RESUBMIT". For those shop drawings, the contractor will be responsible for resubmitting a new print.
 - Catalog Information and Calculations: Submit four copies for City's record and additional numbers of copies required for the contractor's purpose. The City will notify the contractor in writing and return the contractor's copies, with or without notation, marked either "REVIEWED NO EXCEPTIONS TAKEN", "REVISE AND RESUBMIT", OR "REJECTED". Catalog information or calculations marked "REVISE AND RESUBMIT" or "REJECTED" must be resubmitted in the same quantities as originally required.
 - 3. <u>Samples</u>: Submit two samples of requested materials for the City's records and additional samples, if desired, to be returned to the contractor. The City will notify the

- contractor in writing, whether the samples are approved or rejected. If they are rejected, new samples must be resubmitted as originally required.
- 4. Corrections or comments made on the submittals during the review do not relieve the contractor from compliance with requirements of the contract documents. The check is only for review of general conformance with the design concept of the project and general compliance with the information given in the contract documents. Contractors are responsible for conforming and correlating all quantities and dimensions; selecting fabrication processes and techniques of construction; coordinating their work with that of all other trades; and performing their work in a safe manner.
- C. "Or Equal": Whenever the words "or equal" or similar term is used, it shall mean as determined by the Commissioner of Public Works or agent. All drawings, data and bulletins necessary to make an "or equal" determination shall be submitted to the Facilities Manager of Buildings & Fleet Services. Such review shall apply to design only and shall in no way relieve the contractor from the responsibilities as outlined in Item 2B above. Evaluation of "or equal" products will be made at the time of shop drawing submission. Any change required in design and coordination between all contractors, subcontractors, or trades due to the use of "or equal" materials shall become the contractor's responsibility. Any costs for detailed engineering reviews and/or any costs to incorporate "or equal" products will be borne by the contractor.

3. PERMITS:

- A. The City of Milwaukee will provide the general building and occupancy permits.
- B. Contractors shall obtain, from the City of Milwaukee Department of City Development and/or other government or private agencies, all special permits as may be necessary in their work.
- C. Contractors shall obtain all permits to occupy or work in the public way as may be necessary for their work.
- D. Contractors shall notify the City and/or appropriate utilities when making utility connections as part of the project.

4. <u>INSPECTION</u>:

- A. Buildings & Fleet Services will provide daily inspection to verify compliance with contract documents, identify contractors and crews on the job, verify compliance with contract conditions (EBE, residency, wage requirements), and record job progress and conditions.
- B. Contractors shall arrange with the Department of Neighborhood Services/Construction Trades Division and permit issuing agencies for all code compliance inspections as required by all permits including, but not limited to, the general building and all special permits issued by that agency.
- C. Contractors shall arrange with the appropriate City agency for compliance inspections, as required, for all permits including, but not limited to, curb and pavement cuts and patches, and public way occupancy and utility connections.

01500/1

SECTION 01500: JOB SITE UTILITIES, FACILITIES, AND SECURITY

1. SCOPE:

A. Index:

- 1. Scope
- 2. Building Security
- 3 Temporary or Trial Usage
- 4. Occupancy During Construction
- 5. Scaffolding
- 6. Electrical Power
- 7. Water
- 8. Toilet Facilities
- 9. Security and Weather Protection
- 10. Parking

2. BUILDING SECURITY:

A. General:

The Downtown Complex is open to the public from 8:00 AM until 4:45 PM, Monday through Friday, excluding holidays. Since most contracted work takes place outside normal business hours, it is essential that contractors and their City agents understand and abide by security policy.

Outlying buildings are not generally open to the public. Contracted work in these buildings can take place at any time. It is essential that contractors and their City agents understand and abide by security policy.

B. Police Access (General):

- 1. Access to Milwaukee Police Department facilities requires the contractor to meet the following access procedures.
- The Police Department require that all contractors, vendors, visitor or other who intend to do business at any Police Department site must have a background check performed by the Milwaukee Police Department <u>PRIOR</u> to any access.
- 3. All contractors' staff requiring access to the site, including any subcontractors, suppliers or vendors will be required to submit their full name (including full middle name) and birth date to allow the Department to perform the necessary background check. The contractor shall provide a staff list two weeks before work begins. At this time contractor shall provide a brief outline of the work, project schedule, and company contact information (company name, contact name and title, phone number and address).
- 4. To add staff during the course of the project provide the same information as above and allow 48 hours for a response.
- 5. The Contractor will be notified if the worker does not pass the background check.
- 6. Sign in and sign out will be required at all Milwaukee Police Department facilities.

Rev 10/07

C. Scope:

At the beginning of any project, a copy of this policy and procedure statement will be added to the project manual for bid consideration and shall be distributed at the Pre-Construction

Meeting. All City agents/officials responsible for engaging contractors, all contractors, and all subcontractors shall be held responsible for following the procedures.

D. City Agents/Officials:

- 1. Any City agents/officials who commission outside contractors to work in any of the facilities managed by Buildings and Fleet Services shall provide the following information no less than twenty-four (24) hours in advance of the work:
 - The names of any contract or subcontract employees who will be present in the facilities (for the purpose of designing badges appropriate to their work area):

Green – Zeidler Municipal Building, 841 North Broadway Red – City Hall, 200 East Wells Street Yellow – 809 North Broadway Gold – Any outlying buildings

These names must be listed on a sign-in sheet available in the Zeidler Municipal Building, Room 602 (Buildings & Fleet Services support staff — Extension 8222). City agents/officials shall be responsible to ensure the sheet and badges are transported to the appropriate location where the work is to be completed (in the Downtown Complex it would go to the City Hall Information Center, for outlying buildings to the person responsible for controlling access in the facility) the day before work is to begin.

- b. A list of keys and/or access cards required for access only to the areas necessary for work involved in the project. The keys and card will be received from the Security Manager or his designee and signed out to the City agents/officials responsible for the contracted work. The City employee will take the keys and/or access cards to the City Hall Information Center or the person responsible for controlling access in the outlying building where they shall be logged under the name of the contractor's company. When a project is complete, the City agents/officials must retrieve the keys/cards and return them to Buildings & Fleet Services support staff in Room 602 of the Zeidler Municipal Building.
- c. The City agents/officials are responsible for communicating the security policy and procedures to contractors. The City agents/officials shall act as liaison for all communication between Buildings & Fleet Services and the contractor.

E. Contractors:

- 1. Contractors shall abide by City security policy and procedures at all times during the scope of their participation in a project. Failure to comply will result in the contracted employee being escorted from the premises and the resulting lost time and expense shall be deducted from the contractor's invoice or penalties of \$50.00 per occurrence as determined by the contracting City agent/official.
 - a. All access should be provided in advance through the City agent/official. Contractors shall enter and exit only through those doors designated by City agents/officials (the Market Street entrance to City Hall and the doors established by the person responsible for access at outlying buildings). All other exterior doors are locked and alarmed and are not to be used as delivery points unless the City agent/official has been provided 24 hour notification to

01500/3

provide additional security coverage at that point while the delivery is in progress.

- b. All of the contractor's employees and all of the employees of any of his subcontractors shall wear at all times while on the site, in a clearly visible location, an identification card. The identification card is to have a minimum 1" x 1" color photo of the head and shoulders. The photo is to have been taken no more than one year previously. The card is to be laminated with clear plastic and is to contain the company name, employee's name, and the employee's signature, and is to be furnished by the contractor or respective subcontractor.
- c. Effective October 1, 2004 City of Milwaukee Policy Change

The following policy has been established to maintain control of City Property and to ensure the physical protection of the City Hall Complex.

Rev. 9/04

<u>Anyone</u> signing out access cards and/or keys from the Information Center will be following the steps below.

- Sign in on the sheet assigned to the project you are working on and pull that sheet and provide it to the Operator noting that you will need to sign out City property to access the building.
- 2) Provide the Operator your driver's license as collateral for the return of City property.
- 3) Sign out the property in the sign out book as per current policy.
- 4) The Operator will file your driver's license until such time as you sign in and return the City property at which time your license will be returned.
- 5) Sign out at the end of your workday on the sign out sheet.

Under NO circumstances will keys or cards be disbursed without the user signing for the property and providing the City Hall Operator their driver's license as collateral.

In the event that keys or cards are not returned daily the contractor in question will have a deduct (security violation) as per the contract. Individuals who loose or fail to return keys will be responsible for the cost of re-keying to the City.

Contractors will sign in on pre-approved forms and also wear the City identification badges (also to be worn at all times on the premises). Keys or access cards will be signed out as provided by the City agent/official and required for the work. These keys, cards, and badges must be returned at the end of each shift before signing out. Failure to do so will result in a \$50.00 penalty for each occurrence.

d. Contractors shall not ask custodians or mechanics to unlock doors. All access should be provided in advance through the City agent/official. In the rare case

where access is not provided, the City Hall Operator may be contacted to assist in providing access. The contractor shall cooperate with security personnel at all times. The contractor should be prepared to allow searches of equipment when leaving, and should remain only in the areas designated on the sign-in sheets. Security will question a contractor who has an identification badge that indicates a work area other than the area he or she is in.

- e. If the contractor requires use of the loading dock in Upper Parking, 24 hour advance notice shall be given to the City agent/official to make arrangements to provide additional security coverage while the delivery is in progress. The contractor or subcontractor shall meet the delivery driver and take delivery at that point. At no time shall a driver be allowed in the facilities without following the access procedure stated above.
- f. If after normal business hours work is required in the outlying buildings, all subcontractors and trades will arrange appropriate security measures and lock-up procedures with the contractor in writing. Any work completed at night shall be left "open" for City inspection of the work. The contractor shall notify the City agent/official 24 hours in advance of after-hours work in writing, indicating the type of work to be done and the security measures to be taken by the contractor.
- g. The contractor shall provide plywood door and window closures during construction to secure the structure from weather and damage from vandalism. The contractor is responsible to maintain the security of the space where they are working during construction.
- h. If proper notification is not provided to the contractor, the subcontractor or trades shall be liable for any subsequent damage/vandalism/inspection cost, etc., due to lack of security/inspection coordination.
- i. Use of City materials is strictly prohibited unless pre-arranged through the City employee contact.
- At no time shall any interior doors that control access or exterior doors be propped open.

3 TEMPORARY OR TRIAL USAGE:

The owner shall have the right to make temporary or trial usage of any mechanical device, machinery, apparatus, equipment, work, material or construction supplied under contract before final completion or acceptance of the work, and the same shall not be construed as evidence of acceptance of the work by the owner.

OCCUPANCY DURING CONSTRUCTION:

The owner will occupy the premises while work is in progress. Contractor is to coordinate his work as to not interfere with the owner's operation or compromise building security.

5. SCAFFOLDING:

General Contractor shall provide protective sidewalk scaffolding and any additional measures as required to protect the public and allow safe use of this entrance into the facility during the entire construction period.

All scaffolding, swing stages and lifts as required to perform work defined in this contract document shall be provided and maintained by the General Contractor and shall be removed when no longer needed. The General Contractor is solely responsible for the design, safety and security of any scaffolding erected under this contract for this project. All scaffolding, swing stages and lifts shall be available with operators for access to the project for the Project Engineer, City Liaison and City Inspectors.

Exterior scaffolding access (up & down) shall be provided. Access through to the facility will be strictly limited. Adequate security must be provided by the General Contractor to limit the opportunity of unauthorized access of scaffolding.

Submittals for the scaffolding and egress protection shall be provided and reviewed before proceeding with erection. Scaffolding and egress protection submittals shall be stamped by a professional engineer. The scaffolding engineer shall design any foundations or anchoring points as required. The scaffolding system shall be properly grounded.

All anchors and other attachments into building shall be limited. All anchors and attachment shall be clearly indicated on submittals. All costs for scaffolding including installation of anchoring, foundation, erection and patching of all anchor and attachment points at the conclusion of the project shall be included in the base bid. Patching of all anchor or attachment points shall match existing façade materials. On site patching sample shall be provided and approved before proceeding with all patch work. Any damage to sidewalks, pavement or landscaped areas shall be restored to existing preconstruction conditions after the removal of the scaffolding.

Swing stages shall be installed and operated in accordance with all OSHA requirements. rev 10/07

6. ELECTRICAL POWER:

Contractor may use existing outlets for power. Available outlets are 120 and 240 Volt single phase and 480 Volt three phase. Contractor is to supply his own lines. OSHA regulations require that employers use either ground fault circuit interrupters or an assured equipment grounding conductor program in addition to any other regulations for equipment grounding conductors. The cost of the current used will be paid for by the City.

7. WATER:

Contractor may use existing hose bibs for water. Contractor is to supply his own hoses. Contractor's hoses shall be leak free and contractor is to regulate the flow to limit it to project related use. The cost of the water will be paid for by the City.

8. TOILET FACILITIES:

Contractor may use existing toilet facilities in the building.

SECURITY AND WEATHER PROTECTION:

Contractor is to furnish, install, and maintain 8' high, nine gauge steel fence fabric at the exterior of the building, across any door or other openings into the building during construction to maintain security after work hours when not working on these openings. The fabric is to be securely fastened at the sides of the opening. Contractor is also to furnish, install, and maintain a waterproof tarp that completely covers the door opening between the fence and the building fastened to prevent rain from entering the building and secured against wind release. Contractor is to remove the fence fabric and tarp at the

01500/6

completion of each phase of the project when the permanent doors provide security and weather protection.

10. PARKING:

Contractor is responsible for parking of vehicles. No parking areas will be provided by the City.

SECTION 01600: MATERIALS AND EQUIPMENT

SCOPE:

A. Index:

- 1. Scope
- 2. Materials
- 3. Equipment
- 4. Hazardous Material Requirements
- 5. Material Storage
- 6. Protection
- 7. Revisions

MATERIALS:

- A. Furnish materials of the type, qualities, and characteristics specified. The specification of a trade name and catalog number is intended to establish quality, type, character, and operating characteristics of the material required. Materials by other manufacturers of equal specifications will be accepted, excepting as may be specifically stated otherwise.
- B. Materials shall be delivered adequately protected, in merchantable condition, and in original unbroken packages if normally packaged. They shall be stored and handled so as to protect and maintain their merchantable condition.
- C. The Commissioner of Public Works or his representative shall have the right to reject material not in compliance with the project manual, as well as damaged material, and the contractor shall remove such material from the construction site when and as directed.

3. EQUIPMENT:

- A. Internal combustion engine and compressor shall be equipped with mufflers to reduce noise to a minimum and shall not be operated in enclosed areas without adequate ventilation.
- B. All materials and work procedures used shall be in accordance with all air pollution control regulations in effect at the work site.

4. HAZARDOUS MATERIAL REQUIREMENTS:

- A. The requirements set forth in the OSHA Hazard Communication Standard, 29CFR19101.1200, U.S. Environmental Protection Agency (EPA), and Wisconsin Department of Natural Resources in the Wisconsin Administrative Code NR600, shall be met by each on-site contractor.
 - Material Safety Data Sheets (M.S.D.S.):
 - a. All contractors, which may/may not include the City of Milwaukee, shall provide the M.S.D.S. for all hazardous chemicals to which any person may be exposed at the work site.
 - b. A master list will be kept in the office of the Project Supervisor/Construction Manager and updated as materials are delivered.

2. Container Labeling:

01600/2

- Each container of hazardous material at the work site shall be clearly labeled with:
 - (1) Identity of the hazardous chemical(s).
 - (2) Appropriate hazard warning(s).
 - (3) Name and address of the manufacturer.
- B. The City of Milwaukee reserves the right to stop the work of a contractor if compliance with OSHA regulations is inadequate. Work will not proceed until all applicable safety and health procedures are implemented by the contractor.

5. <u>MATERIAL STORAGE</u>:

- A. The storage areas shall be kept in good order and free of all rubbish and debris.
- B. Coordinate the delivery and storage of all materials and equipment with the Buildings & Fleet Services Project Inspector.
- C. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication.
- D. Store and protect products in accordance with manufacturers' instructions.
- E. Store with seals and labels intact and legible.
- F. Store sensitive products in weather tight, climate controlled, enclosures in an environment favorable to product.
- G. For exterior storage of fabricated products, place on sloped supports above ground.
- H. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- Prevent contact with material that may cause corrosion, discoloration, or staining.
- J. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- K. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

6. PROTECTION:

- A. The premises and the work shall be adequately protected from damage from the commencement of work to the date of final acceptance.
- B. All construction work and traffic shall remain within the construction area.
- C. All damage shall be corrected or repaired by the contractor or contractors causing same at his or their own expense.

D. All open pipes, pipe threads, fittings, and insulation must be protected during construction.

7. REVISIONS:

The right is reserved to make modifications to a reasonable extent as building conditions may require, or as may be required to conform to code rulings, or manufacturer's standards without extra cost to the City.

SECTION 01700: CLEANING AND PROJECT CLOSE-OUT

1. SCOPE:

A. Index:

- 1. Scope
- 2. General
- 3. Safety Cleaning
- 4. Progress Cleaning
- 5. Disposal
- 6. Final Cleaning
- 7. Charges
- 8. Guarantees

2. GENERAL:

Article 2.5.4 of the General Requirements of City of Milwaukee Department of Public Works shall be supplemented as specified hereinafter.

3. <u>SAFETY CLEANING:</u>

Safety cleaning: Each contractor is responsible for safety cleaning, which includes but is not limited to the following:

- A. Keep work areas, passageways, ramps, stairs, free of debris and scrap.
- B. Form and scrap lumber shall have nails withdrawn or bent over and lumber shall be stacked or removed.
- Remove spills of oil, grease, or other liquids immediately or sprinkle with sand.
- D. Hazardous material shall be handled in accordance with Section 01600. Each container of hazardous material at the work site shall be clearly labeled with:
 - a. Identity of the hazardous chemical(s).
 - b. Appropriate hazard warning(s).

4. PROGRESS CLEANING:

- A. Prime Contractor and subcontractor shall remove his rubbish and debris from building site promptly upon its accumulation, and prior to the contractor's regular Friday general clean up. Contractor shall perform broom cleaning of all appropriate surfaces each Friday afternoon.
- B. Combustible waste shall be stored in fire resistive containers and disposed of regularly.
- C. Oily, flammable or hazardous wastes such as caustics, acids, harmful dusts, etc., shall be stored in appropriate covered containers.

5. <u>DISPOSAL</u>:

A. No burning of rubbish or debris will be allowed at site. No rubbish shall be thrown through opening or from heights without proper protection. Where dust will be generated or flying

- debris is likely to occur, provide dust tight chutes or other means to control dust.
- B. <u>Containers</u>: Contractor shall provide mobile industrial type waste containers in the number and size required, placed at adequate locations to handle debris or provide other methods of disposing of debris.
- C. Oil, flammable or hazardous wastes such as, but not limited to, caustics, acids, harmful dusts, etc., shall be placed in properly marked containers as necessary and disposed of at a site designed for such wastes.

6. FINAL CLEANING:

- A. Immediately prior to substantial completion.
- B. Contractors shall expedite or perform thorough cleaning, sweeping, washing and polishing of work to remove from work and equipment provided under his contract, all foreign matter, spots and soil, so as to put all such work and equipment, including finishes, in a complete and finished condition ready for acceptance and use intended.
- C. The contractor is responsible for final sweeping and dusting not covered by other subcontractors. This general cleaning shall include all areas and floors of the building, including the site outside the building.

7. CHARGES:

- A. If prime contractors do not remove rubbish or clean building as specified above, owner reserves right to have work done by others at contractor's expense.
- B. Employees of the owner who are required to clean up any rubbish or to sweep any floors will record all hours involved to complete such work. The cost incurred by the owner for this special cleaning and sweep-up work shall be charged against the contract price of the contractor as determined by owner.

8. **GUARANTEES**:

- A. Each contractor shall guarantee to replace or repair promptly at his own expense, as directed by the Commissioner of Public Works or his agent, all workmanship or materials in which defects may develop within one (1) year from the date of final acceptance of his work. This guarantee includes all damage done to the City due to faulty equipment, poor installation or poor construction.
- B. Guarantee periods other than the one year time period are indicated in specific specification sections.

SECTION 09 65 00 - RESILIENT FLOORING

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes
 - 1. Resilient tile and sheet flooring
 - 2. Resilient stair treads, risers, and nosings.
- B. Related Sections
 - 1. N.A.

1.2 REFERENCES

- A. American Society for Testing and Materials:
 - 1. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials.
 - 2. ASTM E662 Standard Test Method for Specific Optical Density of Smoke Generated by Solid Materials.
 - 3. ASTM F1066 Standard Specification for Vinyl Composition Floor Tile.
 - 4. ASTM F1861 Standard Specification for Resilient Wall Base.
- B. Federal Specification Unit:
 - 1. FS L-F-475 Floor Covering Vinyl, Surface (Tile and Roll), with Backing.
 - 2. FS RR-T-650 Treads, Metallic and Nonmetallic, Skid Resistant.
- C. National Fire Protection Association:
 - 1. NFPA 253 Standard Method of Test for Critical Radiant Flux for Floor Covering Systems Using a Radiant Heat Energy Source.

1.3 PERFORMANCE REQUIREMENTS

- A. Conform to applicable code for fire performance ratings as follows:
 - 1. Flooring, critical Radiant Flux: ASTM E648; Class I, minimum 0.45 W/sq cm.
 - 2. Flooring, smoke developed: Maximum 450, per ASTM E662.
 - 3. Wall base, flame spread: Maximum 75, per ASTM E84.
 - 4. Wall base, smoke developed: Maximum 450, per ASTM E84.

1.4 SUBMITTALS

- A. Section 01 33 00 Submittal Procedures: Submittal procedures.
- B. Shop Drawings: Indicate seaming plan and custom pattern.
- C. Product Data: Submit data describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.
- D. Samples:
 - 1. Submit two samples, illustrating color and pattern for each resilient flooring product specified.

1.5 CLOSEOUT SUBMITTALS

- A. Division 1 Execution Requirements: Closeout procedures.
- B. Operation and Maintenance Data: Submit maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning, stripping, and re-waxing.

1.6 QUALIFICATIONS

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years experience.
- B. Installer: Company specializing in performing Work of this section with minimum three years experience.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Division 1 Product Requirements: Product storage and handling requirements.
- B. Protect roll materials from damage by storing on end. Protect tile materials from damage by storing on a flat surface.

1.8 ENVIRONMENTAL REQUIREMENTS

- A. Section 01 60 00 Product Requirements.
- B. Maintain temperature in storage area between 55 degrees F, and 90 degrees F.
- C. Store materials for not less than 48 hours prior to installation in area of installation at temperature of 70 degrees to achieve temperature stability. Thereafter, maintain conditions above 55 degrees.

1.9 EXTRA MATERIALS

- A. Division 1 Execution Requirements: Spare parts and maintenance products.
- B. Furnish T.B.D.

PART 2 PRODUCTS

2.1 RESILIENT TILE FLOORING

- A. Manufacturers:
 - 1. Mannington Commercial.
 - 2. Substitutions: No Products will be per approved before bid. The architect will make the Determination of equal product substitution.
- B. Vinyl Composition Tile: ASTM F1066:
 - 1. Materials: Refer to drawing sheet A120-A for product and color listing.
 - a. Finish: Smooth.

RESILIENT FLOORING 09 65 00 - 2

- b. Class 2 through pattern
- c. Type IV.
- d. Thickness: 1/8 inch.
- e. Static Load Limit: 125 p.s.i.
- f. Size: 12" x 12"

2.2 ACCESSORIES

- A. Subfloor Filler: White premix latex; type recommended by adhesive material manufacturer.
- B. Primers and Adhesives: Waterproof; types recommended by flooring manufacturer.
- C. Moldings and Edge Strips: Same material as flooring.
- D. Sealer and Wax: Types recommended by flooring manufacturer.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify concrete floors are dry to maximum moisture content as recommended by manufacturer, and exhibit negative alkalinity, carbonization, and dusting.
- B. Verify floor and lower wall surfaces are free of substances capable of impairing adhesion of new adhesive and finish materials.
- C. Verify that air, substrate, and material temperatures are within manufacturer's recommended ranges.

3.2 PREPARATION

- A. Remove sub-floor ridges and bumps. Fill minor low spots, cracks, joints, holes, and other defects with sub-floor filler to achieve smooth, flat, hard surface.
- B. Patch wall at removed vinyl base. Fill cracks, joints, holes, and other defects with filler to achieve smooth flat, hard surface.
- C. Prohibit traffic until filler is cured.
- D. Clean substrate.

3.3 PREPARATION

- A. Smooth concrete surfaces, removing rough areas, projections, ridges, and bumps, and filling low spots, control or construction joints as recommended by the flooring manufacturer.
- B. Remove paint, varnish, oils, release agents, sealers, and waxes. Remove residual adhesives as recommended by the flooring manufacturer. Remove curing and hardening

- compounds not compatible with the adhesives used, as indicated by a bond test or by the compound manufacturer's recommendations for flooring. Avoid organic solvents.
- C. Perform subfloor moisture testing in accordance with ASTM F 2170, "Standard Test Method for Determining Relative Humidity in Concrete Slabs Using *in-situ* Probes" and Bond Tests to determine if surfaces are dry; free of curing and hardening compounds, old adhesive, and other coatings; and ready to receive flooring.
- D. Vacuum or broom-clean surfaces to be covered immediately before the application of flooring. Make subfloor free from dust, dirt, grease, and all foreign materials.

3.4 INSTALLATION - TILE FLOORING

- A. Install tile in accordance with manufacturer's instructions.
- B. Mix tile from container to ensure shade variations are consistent when tile is placed.
- C. Spread only enough adhesive to permit installation of materials before initial set.
- D. Set flooring in place, press with heavy roller to attain full adhesion.
- E. Lay flooring with joints and seams to building lines to produce symmetrical tile pattern.
- F. Install tile to pattern indicated. Allow minimum 1/2 full size tile width at room or area perimeter.
- G. Scribe flooring to walls, columns, cabinets, floor outlets, and other appurtenances to produce tight joints.
- H. Where floor finishes are different on opposite sides of door, terminate flooring under centerline of door.
- I. Install edge strips at unprotected or exposed edges, where flooring terminates, and where indicated.
- J. At movable partitions, install flooring under partitions without interrupting floor pattern.
- K. Final waxing of floors to be by Contractor.

3.5 INSTALLATION – SHEET RUBBER

A. Comply with manufacturer's technical manual for installation procedures, floor preparation, and substrate testing.

3.6 INSTALLATION - BASE

- A. Fit joints tightly and make vertical. Maintain minimum dimension of 18 inches between joints.
- B. Miter internal corners. At external corners, 'V' cut back of base strip to 2/3 of its thickness and fold. At exposed ends, use premolded units.

RESILIENT FLOORING 09 65 00 - 4

- C. Install base on solid backing. Bond tightly to wall and floor surfaces.
- D. Scribe and fit to door frames and other interruptions.

3.7 INSTALLATION – TRANSITION STRIPS

- A. Install at all material transitions where metal transition strips are not provided.
- B. Fit accurately and securely, following manufacturer's installation recommendations.

3.8 INSTALLATION - STAIR COVERINGS

- A. Install stair nosing, stair treads, and stair risers in one piece for full width and depth of tread.
- B. Install stringers configured tightly to stair profile.
- C. Adhere over entire surface. Fit accurately and securely.

3.9 CLEANING

- A. Remove excess adhesive from floor, base, and wall surfaces without damage.
- B. Clean resilient flooring products per manufacturer's standards.

3.10 PROTECTION OF INSTALLED CONSTRUCTION

- A. Division 1 Execution Requirements: Protecting installed construction.
- B. Prohibit traffic on resilient flooring for 48 hours after installation.

END OF SECTION 09 65 00

SECTION 09 65 13 - RESILIENT BASE

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - Resilient base.
- B. Related Sections:
 - 1. Division 09 Section "Resilient Tile Flooring" for resilient floor tile.
 - 2. Division 09 Section "Tile Carpeting" for carpet flooring.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples for Verification: For each type of product indicated, in manufacturer's standard-size Samples but not less than 12 inches long, of each resilient product color, texture, and pattern required.
- C. Product Schedule: For resilient products.

1.3 QUALITY ASSURANCE

- A. Fire-Test-Response Characteristics: As determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
 - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.

1.5 PROJECT CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following time periods:
 - 1. 48 hours before installation.
 - 2. During installation.

- 3. 48 hours after installation.
- B. Install resilient products after other finishing operations, including painting, have been completed.

1.6 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Furnish not less than 10 linear feet for every 500 linear feet or fraction thereof, of each type, color, pattern, and size of resilient product installed.

PART 2 - PRODUCTS

2.1 RESILIENT BASE

- A. Resilient Base:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the following:
 - a. Johnsonite Traditional Wall Base
- B. Resilient Base Standard: ASTM F 1861.
 - 1. Material Requirement: Type TP (rubber, thermoplastic).
 - 2. Manufacturing Method: Group I (solid, homogeneous).
 - 3. Style: Cove (base with toe) at resilient flooring locations (refer to drawings)
 - 4. Style: Straight (toeless base) at carpet flooring locations (refer to drawings)
- C. Minimum Thickness: 0.080 inch.
- D. Height: 6".
- E. Lengths: Coils in manufacturer's standard length.
- F. Outside Corners: Job formed.
- G. Inside Corners: Job formed.
- H. Finish: As selected by Architect from manufacturer's full range.
- I. Colors and Patterns: As indicated by manufacturer's designations on drawings.

2.2 INSTALLATION MATERIALS

A. Adhesives: Water-resistant type recommended by manufacturer to suit resilient products and substrate conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound and remove bumps and ridges to produce a uniform and smooth substrate.
- C. Do not install resilient products until they are same temperature as the space where they are to be installed.
 - 1. Move resilient products and installation materials into spaces where they will be installed at least 48 hours in advance of installation.
- D. Sweep and vacuum clean substrates to be covered by resilient products immediately before installation.

3.3 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practicable without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.
- G. Job-Formed Corners:

- 1. Outside Corners: Use straight pieces of maximum lengths possible. Form without producing discoloration (whitening) at bends.
- 2. Inside Corners: Use straight pieces of maximum lengths possible.

3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protection of resilient products.
- B. Perform the following operations immediately after completing resilient product installation:
 - 1. Remove adhesive and other blemishes from exposed surfaces.
 - 2. Sweep and vacuum surfaces thoroughly.
 - 3. Damp-mop surfaces to remove marks and soil.
- C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

END OF SECTION 09 65 13

SECTION 09 68 13 - TILE CARPETING

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes modular, tufted carpet tile.

1.2 SUBMITTALS

- A. Product Data: For each product indicated.
- B. Shop Drawings: Show the following:
 - 1. Carpet tile type, color, and dye lot.
 - 2. Pattern of installation.
 - 3. Edge, transition, and other accessory strips.
 - 4. Transition details to other flooring materials.
- C. Samples: For each color and texture required.
 - 1. Carpet Tile: Full-size Sample.
 - 2. Exposed Edge, Transition, and other Accessory Stripping: 12-inch-long Samples.
- D. Product Schedule: For carpet tile. Use same designations indicated on Drawings.
- E. Maintenance data.

1.3 QUALITY ASSURANCE

A. Installer Qualifications: An experienced installer who is certified by the Floor Covering Installation Board or who can demonstrate compliance with its certification program requirements.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Comply with CRI 104, Section 5, "Storage and Handling."

1.5 PROJECT CONDITIONS

- A. Comply with CRI 104, Section 7.2, "Site Conditions; Temperature and Humidity" and Section 7.12, "Ventilation."
- B. Environmental Limitations: Do not install carpet tiles until wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

TILE CARPETING 09 68 13 - 1

- C. Do not install carpet tiles over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet tile manufacturer.
- D. When installing carpeting over existing VCT, existing surface is to be prepared as recommended by manufacturer. Any stripping of existing finishes is to be with non-solvent stripper. Any preparatory materials and process is to be included with submittals and approved before proceeding.
- E. Where demountable partitions or other items are indicated for installation on top of carpet tiles, install carpet tiles before installing these items.

1.6 WARRANTY

- A. Special Warranty for Carpet Tiles: Manufacturer's standard form in which manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period. Failures include, but are not limited to, more than 10 percent loss of face fiber, edge raveling, snags, runs, loss of tuft bind strength, dimensional stability, and delamination.
 - 1. Warranty Period: 10 years from date of Substantial Completion.

1.7 EXTRA MATERIALS

- A. Furnish extra materials described below, before installation begins, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Carpet Tile: Full-size units equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd..

PART 2 - PRODUCTS

2.1 CARPET TILE:

- A. Products: Subject to compliance with requirements, provide one of the following:
 - 1. As indicated on drawings.
 - a. Manufacturer: Tandus Flooring, as indicated on drawings
 - b. Product: "Landform", as indicated on drawings
 - c. Color: As selected or indicated on drawings by Architect from manufacturer's full range.

B. Face Weight: 20 zo/square yard

TILE CARPETING 09 68 13 - 2

- C. Gauge: 5/64
- D. Stitches per inch: 10.6
- E. Fiber System: Antron Lumena Nylon
- F. Primary Backing/Backcoating: ER# with RS Adhesive
- G. Size: 24" x 24"

2.2 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended by carpet tile manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet tile and is recommended by carpet tile manufacturer for releasable installation.
 - 1. VOC Limits: Provide adhesives with VOC content not more than 50 g/L when calculated according to 40 CFR 59, Subpart D (EPA method 24).

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Comply with CRI 104, Section 14, "Carpet Modules," and with carpet tile manufacturer's written installation instructions.
- B. Installation Method: As recommended in writing by carpet tile manufacturer.
- C. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- D. Install pattern parallel to walls and borders.

END OF SECTION 09 68 13

TILE CARPETING 09 68 13 - 3

	•		